

6/5/2023 9:21 AM
z:\projects\windsor windows and doors\cc-22-1132 - fbc 2023 code change\dwgs\fl11573.1\wwd033.dwg

INSTALLATION NOTES:

1. ONE (1) INSTALLATION ANCHOR IS REQUIRED AT EACH ANCHOR LOCATION SHOWN.
2. THE NUMBER OF INSTALLATION ANCHORS DEPICTED IS THE MINIMUM NUMBER OF ANCHORS TO BE USED FOR PRODUCT INSTALLATION OF THE MAXIMUM SIZE LISTED.
3. INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF ±1/2 INCH BASED ON QUANTITIES IN DP CHARTS NOT TO EXCEED THE DEPICTED LOCATION & SPACING IN THE ANCHOR LAYOUT DETAILS (I.E., WITHOUT CONSIDERATION OF TOLERANCES). TOLERANCES ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT
4. SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM(S). MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4 INCH. SHIM WHERE SPACE OF 1/16 INCH OR GREATER OCCURS. SHIM(S) SHALL BE CONSTRUCTED OF HIGH DENSITY PLASTIC OR BETTER.
5. **THROUGH FRAME:** FOR INSTALLATION INTO WOOD FRAMING USE #10 WOOD SCREWS OF SUFFICIENT LENGTH TO ACHIEVE 1 1/2" MINIMUM EMBEDMENT INTO WOOD SUBSTRATE.
6. **THROUGH FRAME:** FOR INSTALLATION THROUGH 1X BUCK TO CONCRETE/MASONRY, OR DIRECTLY INTO CONCRETE/MASONRY, USE 1/4" DIAMETER ITW TAPCONS, ELCO ULTRACONS, ELCO CRETE-FLEX OR HILTI KWIK-CON II OF SUFFICIENT LENGTH TO ACHIEVE 1 1/4" MINIMUM EMBEDMENT.
7. **THROUGH FRAME:** FOR INSTALLATION INTO METAL STUD OR APPROVED MULLION USE #10 GR. 5 SELF TAPPING SCREWS OF SUFFICIENT LENGTH TO ACHIEVE A MINIMUM OF 3 THREADS PENETRATION BEYOND METAL FRAME SUBSTRATE.
8. CLIPS SHALL BE FASTENED TO THE WINDOW FRAME WITH (2) #8 X 5/8" SCREWS. CLIPS ARE 20 GAUGE (0.063" THICKNESS) F_y=33 KSI MIN STEEL WITH OVERALL DIMENSIONS OF 1.5" WIDE, 7.813" ALONG THE LONG LEG, AND 1.942" ALONG THE SHORT LEG.
9. **CLIP ANCHOR:** FOR INSTALLATION INTO METAL STUD USE (2) #8 GR. 5 SELF-TAPPING SCREWS PER CLIP OF SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM PENETRATION BEYOND THE METAL STRUCTURE.
10. **CLIP ANCHOR:** FOR INSTALLATION INTO WOOD FRAMING USE (2) #8 WOOD SCREWS PER CLIP OF SUFFICIENT LENGTH TO ACHIEVE 1 1/2 INCH MINIMUM EMBEDMENT INTO WOOD SUBSTRATE.
11. **NAIL FIN:** FOR INSTALLATION INTO WOOD FRAMING USE #8 WOOD SCREWS OR USE 10D COMMON NAIL OR 11 GAUGE ROOFING NAIL PER LOCATION OF SUFFICIENT LENGTH TO ACHIEVE 1 1/2 INCH MINIMUM EMBEDMENT INTO WOOD SUBSTRATE.
12. NAIL FIN: FOR INSTALLATION INTO METAL STUD USE #8 GR.5 SELF-TAPPING SCREWS OF SUFFICIENT LENGTH TO ACHIEVE 3 THREADS MINIMUM PENETRATION BEYOND THE METAL STRUCTURE.
13. MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
14. INSTALLATION ANCHORS AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING.
15. FOR GROUT FILLED BLOCK, DO NOT INSTALL INSTALLATION ANCHORS INTO MORTAR JOINTS. EDGE DISTANCE IS MEASURED FROM FREE EDGE OF BLOCK OR EDGE OF MORTAR JOINT INTO FACE SHELL OF BLOCK.
16. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER.

WINDSOR WINDOWS & DOORS

PINNACLE CLAD INSWING DOOR

(WZ3) (IMPACT)

GENERAL NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT FLORIDA BUILDING CODE (FBC), EXCLUDING HVHZ AND HAS BEEN EVALUATED ACCORDING TO THE FOLLOWING:
 - AAMA/WDMA/CSA 101/I.S.1/A440-11
 - ASTM E1886-13a
 - ASTM E1996-14a
2. ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY AND 2X FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
3. 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
4. THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT.
5. APPROVED IMPACT PROTECTIVE SYSTEM **IS NOT REQUIRED** ON THIS PRODUCT IN WIND ZONES 3 OR LESS.
6. APPROVED IMPACT PROTECTIVE SYSTEM **IS REQUIRED** ON THIS PRODUCT IN WIND ZONE 4.
7. DOOR FRAME MATERIAL:

7.1. WOOD

7.2. ALUMINUM 6063-T5
8. DISSIMILAR METALS INCLUDING FASTENERS THAT MAY COME INTO CONTACT WITH ALUMINUM COMPONENTS SHALL BE PROTECTED IN ACCORDANCE WITH THE FBC.
9. DESIGNATIONS "X" AND "O" STAND FOR THE FOLLOWING:

X: OPERABLE PANEL

O: STATIONARY PANEL

TABLE OF CONTENTS	
SHEET	SHEET DESCRIPTION
1	INSTALLATION & GENERAL NOTES
2	ELEVATIONS
3	ANCHOR LAYOUTS
4	ANCHOR LAYOUTS (SINGLE DOOR)
5	HORIZONTAL SECTION
6	VERTICAL SECTION
7	HORIZONTAL SECTION
8	HORIZONTAL SECTION (NARROW STILE)
9	GLAZING & MULLION DETAILS

DESIGN PRESSURE TABLE						
TYP. OVERALL FRAME SIZE		TYP. OVERALL PANEL SIZE		DESIGN PRESSURE	MISSILE IMPACT RATING	WIND ZONE
MAX FRAME WIDTH	MAX. FRAME HEIGHT	MAX PANEL WIDTH	MAX. PANEL HEIGHT			
75.00"	95 ³ / ₈ "	36.00"	93.00"	+50/-50 PSF	MISSILE LEVEL D	WZ3



WINDSOR WINDOWS & DOORS

900 S. 19TH STREET.
WEST DES MOINES, IA 50265
PH: (515)223-6660 FAX: (515)224-1938

TITLE:

PINNACLE CLAD INSWING DOOR (WZ3) (IMPACT)

INSTALLATION & GENERAL NOTES

PREPARED BY:


BUILDING DROPS, INC.

398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com

BUILDING DROPS

REMARKS	BY	DATE
NARROW STILE	YC	01/20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:

FL11573

DATE: 01.02.2020

DWG. BY: YC

CHK. BY: HFN

SCALE: NTS


DWG. #: WWD033

SHEET:


1

OF 9


6/5/2023 9:21 AM
z:\projects\windsor windows and doors\cc-22-1132 - fbc 2023 code change\dwgs\fl11573.1\wwd033.dwg



TYPICAL ELEVATION
BI-HINGE




TYPICAL ELEVATION
STATIONARY-ACTIVE




TYPICAL ELEVATION
SINGLE DOOR

QUALIFIED CONFIGURATIONS

- NOTES:
- SIZES BELOW INDICATES PANEL MAXIMUM PANEL WIDTH FOR CONFIGURATIONS.
 - SIDELITES UNDER SEPARATE APPROVAL.



SIDELITE W/ NARROW STILE
QUALIFIED CONFIGURATIONS



- NOTES:
- SIDELITES USING 2 1/4" STILE SHOULD NOT EXCEED 16" OF PANEL SIZE WIDTH.
 - SIDELITES UNDER SEPARATE APPROVAL.

NOTES:

- MAXIMUM DESIGN PRESSURE FOR NARROW STILE SIDELITE ON SHEET 2 SHOULD BE AS PER DESIGN PRESSURE TABLE AND A MAXIMUM D.L.O. OF 11.5" X 102.50".
- NARROW STILE SIDELITES AND TRADITIONAL SIDELITES UNDER SEPARATE APPROVAL. THE LOWER DESIGN PRESSURE OF THE DOOR AND SIDELITE SHALL CONTROL THE ALLOWABLE DESIGN PRESSURE FOR THE ASSEMBLY.



WINDSOR WINDOWS & DOORS

900 S. 19TH STREET.
WEST DES MOINES, IA 50265
PH: (515)223-6660 FAX: (515)224-1938

PINNACLE CLAD
INSWING DOOR
(WZ3) (IMPACT)
ELEVATIONS

TITLE:


PREPARED BY:

BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
NARROW STILE	YC	01/20


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL11573
DATE:	01.02.2020
DWG. BY:	YC
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	WWD033
SHEET:	2

6/5/2023 9:21 AM


z:\projects\windsor windows and doors\cc-22-1132 - fbc 2023 code change\dwgs\fl11573.1\www033.dwg




TYPICAL ANCHOR LAYOUT
BI-HINGE (NAIL FIN)



TYPICAL ANCHOR LAYOUT
BI-HINGE (THROUGH FRAME)




TYPICAL ANCHOR LAYOUT
BI-HINGE (CLIP INSTALLATION)




TYPICAL ANCHOR LAYOUT
STATIONARY- ACTIVE (NAIL FIN)

NOTE:
USE NAIL FIN AT HEAD AND
SIDE JAMBS, USE THRU FRAME
INSTALLATION METHOD AT SILL



TYPICAL ANCHOR LAYOUT
STATIONARY- ACTIVE (THROUGH FRAME)



TYPICAL ANCHOR LAYOUT
STATIONARY- ACTIVE (CLIP INSTALLATION)



**WINDSOR WINDOWS
& DOORS**
900 S. 19TH STREET.
WEST DES MOINES, IA 50265
PH: (515)223-6660 FAX: (515)224-1938


TITLE:
PINNACLE CLAD
INSWING DOOR
(WZ3) (IMPACT)
ANCHOR LAYOUTS

PREPARED BY:
BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
NARROW STILE	YC	01/20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL11573
DATE:	01.02.2020
DWG. BY:	YC
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	WWD033
SHEET:	

3

OF 9







TYPICAL ELEVATIONS SHOWN ABOVE SHOW MAXIMUM FRAME SIZE FOR BI-HINGE AND STA-ACT CONFIGURATIONS. NARROW STILE CONFIGURATIONS STATED ON SHEET 1 DESIGN PRESSURE TABLE SHALL HAVE MAXIMUM ALLOWABLE DLO DIMENSIONS OF 29.25" X 81.875".

NOTE:
USE NAIL FIN AT HEAD AND
SIDE JAMBS, USE THRU FRAME
INSTALLATION METHOD AT SILL



6/5/2023 9:21 AM
z:\projects\windsor windows and doors\cc-22-1132 - fbc 2023 code change\dwgs\fl11573.1\www033.dwg



WINDSOR WINDOWS & DOORS

900 S. 19TH STREET.
WEST DES MOINES, IA 50265
PH: (515)223-6660 FAX: (515)224-1938


TITLE: PINNACLE CLAD
INSWING DOOR
(WZ3) (IMPACT)
VERTICAL SECTIONS

PREPARED BY: BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com




REMARKS	BY	DATE
NARROW STILE	YC	01/20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL11573
DATE:	01.02.2020
DWG. BY:	YC
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	WWD033
SHEET:	5


6/5/2023 9:21 AM
z:\projects\windsor windows and doors\cc-22-1132 - fbc 2023 code change\dwgs\fl11573.1\wwd033.dwg




A
6 VERTICAL SECTION
HEAD - THROUGH FRAME INSTALLATION



B
6 VERTICAL SECTION
HEAD - THROUGH FRAME INSTALLATION



C
6 VERTICAL SECTION
HEAD - CLIP INSTALLATION



D
6 VERTICAL SECTION
HEAD - CLIP FRAME INSTALLATION



**WINDSOR WINDOWS
& DOORS**
900 S. 19TH STREET.
WEST DES MOINES, IA 50265
PH: (515)223-6660 FAX: (515)224-1938


TITLE:
PINNACLE CLAD
INSWING DOOR
(WZ3) (IMPACT)
VERTICAL SECTIONS

PREPARED BY:
BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
NARROW STILE	YC	01/20


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC
AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC
SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE
FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED
ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC
DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL11573
DATE:	01.02.2020
DWG. BY:	YC
CHK. BY:	HFN
SCALE:	NTS
DWG. #:	WWD033
SHEET:	6

6/5/2023 9:21 AM


z:\projects\windsor windows and doors\cc-22-1132 - fbc 2023 code change\dwgs\fl11573.1\wwd033.dwg



A HORIZONTAL SECTION
7 JAMB - FIN INSTALLATION

B HORIZONTAL SECTION
7 (BI-HINGE - ASTRAGAL)

C HORIZONTAL SECTION
7 JAMB - FIN INSTALLATION



D HORIZONTAL SECTION
7 JAMB - THROUGH FRAME INSTALLATION

E HORIZONTAL SECTION
7 STA-ACT ASTRAGAL

F HORIZONTAL SECTION
7 JAMB - THROUGH FRAME INSTALLATION

CONFIGURATION NOTES:

BI-HINGE SECTION DETAILS SHOWN IN COMBINATION WITH NARROW STILE PROFILES, STA-ACT SECTION DETAILS SHOWN IN COMBINATION WITH REGULAR STILE PROFILES. DETAILS ARE INTENDED TO BE REPRESENTATIVE AND MAY BE INTERMIXED IN ACCORDANCE WITH CONFIGURATIONS STATED ON SHEET 1 DESIGN PRESSURE TABLE.



WINDSOR WINDOWS
& DOORS

900 S. 19TH STREET.
WEST DES MOINES, IA 50265
PH: (515)223-6660 FAX: (515)224-1938

PINNACLE CLAD
INSLING DOOR
(WZ3) (IMPACT)
HORIZONTAL SECTIONS


TITLE:

PREPARED BY:
BUILDING DROPS, INC.
398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com



REMARKS	BY	DATE
NARROW STILE	YC	01/20


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:	FL11573
DATE:	01.02.2020
DWG. BY:	CHK. BY:
YC	HFN
SCALE:	NTS
DWG. #:	WWD033
SHEET:	7

6/5/2023 9:21 AM


z:\projects\windsor windows and doors\cc-22-1132 - fbc 2023 code change\dwgs\fl11573.1\wwd033.dwg



A **HORIZONTAL SECTION**
8 JAMB - THROUGH FRAME INSTALLATION

B **HORIZONTAL SECTION**
8 STA-ACT ASTRAGAL

C **HORIZONTAL SECTION**
8 JAMB - THROUGH FRAME INSTALLATION



D **HORIZONTAL SECTION**
8 JAMB - NAIL FIN INSTALLATION

E **HORIZONTAL SECTION**
8 STA-ACT ASTRAGAL

F **HORIZONTAL SECTION**
8 JAMB - THROUGH FRAME INSTALLATION



WINDSOR WINDOWS & DOORS

900 S. 19TH STREET.
WEST DES MOINES, IA 50265
PH: (515)223-6660 FAX: (515)224-1938

PINNACLE CLAD
INSWING DOOR
(WZ3) (IMPACT)
HORIZONTAL SECTION
(NARROW STILE)


PREPARED BY:
BUILDING DROPS, INC.

398 E. DANIA BEACH BLVD., STE. 338
DANIA BEACH, FL 33004
PH: (954)399-8478
FAX: (954)744-4738
WEB: www.buildingdrops.com




REMARKS	BY	DATE
NARROW STILE	YC	01/20


THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT




FL #:	FL11573
DATE:	01.02.2020
DWG. BY:	CHK. BY:
YC	HFN
SCALE:	NTS
DWG. #:	WWD033
SHEET:	8



BACK TO BACK MULLION
ACTIVE/ACTIVE




BACK TO BACK MULLION
ACTIVE/INACTIVE



BACK TO BACK MULLION
ACTIVE/INACTIVE

3/4" O.A. THICKNESS INSULATED GLASS CONSISTING OF:
1/8" TEMPERED GLASS
5/16" AIR SPACE
3/32" TEMPERED GLASS
.090 SAFLEX PVB INTERLAYER BY EASTMAN CHEMICAL CO.
3/32" TEMPERED GLASS



NOTES:

- SETTING BLOCK DUROMETER HARDNESS OF 70-90 (SHORE A) AS REFERENCED IN CHAPTER 24.
- SETTING BLOCKS TO BE LOCATED AT 1/4 SPAN LENGTH FOR GLASS WIDER THAN 36" AS PER CHAPTER 24.




WINDSOR WINDOWS & DOORS

900 S. 19TH STREET.
WEST DES MOINES, IA 50265
PH: (515)223-6660 FAX: (515)224-1938

TITLE: PINNACLE CLAD INSWING DOOR (WZ3) (IMPACT) GLAZING & MULLION DETAIL	PREPARED BY: BUILDING DROPS, INC. 398 E. DANIA BEACH BLVD., STE. 338 DANIA BEACH, FL 33004 PH: (954)399-8478 FAX: (954)744-4738 WEB: www.buildingdrops.com

REMARKS	BY	DATE
NARROW STILE	YC	01/20

THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT



FL #:
FL11573

DATE: **01.02.2020**

DWG. BY: YC	CHK. BY: HFN
-----------------------	------------------------

SCALE: **NTS**

DWG. #: **WWD033**

SHEET:

9

OF 9